



Site Remediation
Waste Management
Licensed Transportation
Industrial Landfills
Soil Treatment
Water Treatment
Remediation Systems
Emergency Response
Facility Demolition
Equipment Rentals

www.hazco.com

Project Value: >\$25,000,000

Date: August – November 2005

Contaminant: Bunker "C"
Pole Treatment Oil

HAZCO Key Team Members:
Kevin Bloom

Owner: CN Rail

Consultant: ECRC
Eastern Canadian Response Cooperation

Project Highlights

- Hazco was retained by CN rail to contain and clean up the 770,000 liters of Bunker "C" and the 30,000 liters of Pole treating oil that was spilled at Lake Wabamum.
- Crews and equipment were mobilized from BC and Alberta. Hazco managed a total of 180 crewmembers including sub contractors on site for the lake clean up.
- Materials for the clean up were shipped from as far as Louisiana and Eastern Canada via chartered plane and truck.
- 77,000 feet of containment boom and 513,000 feet of absorbent boom were deployed on Wabamum Lake to contain the Bunker "C" and to protect sensitive areas on the Lake.
- Skimmers, mini vacs and vacuum trucks were deployed to remove the Bunker "C" from the Lake.
- Excavators were used at the derailment site to remove more than 17,000 tonnes of Bunker "C" contaminated soil

