



Site Remediation  
Waste Management  
Licensed Transportation  
Industrial Landfills  
Soil Treatment  
Water Treatment  
Remediation Systems  
Emergency Response  
Facility Demolition  
Equipment Rentals

### PROJECT HIGHLIGHTS

- ❑ Excavation, transportation and disposal of hydrocarbon impacted soils totalling approximately 260,000 tonnes
- ❑ Extensive excavation dewatering and water treatment
- ❑ Design and installation of approximately 1 km of bentonite cut-off walls
- ❑ Operation and maintenance of a 250 GPM water treatment plant

As part of an overall site remediation program, over the past 4 years HAZCO has completed multiple stages of excavation, transportation and disposal of hydrocarbon impacted soils totaling approximately 260,000 tonnes. Completion of the project works requires extensive excavation dewatering and water treatment. Project works have also included the design and installation of approximately 1 km of bentonite cut-off walls to prevent recontamination of remediated areas.

HAZCO currently provides full time operation and maintenance of the sites large-scale water treatment system for the site. Groundwater is recovered from different areas of the overall project site utilizing both submersible pumps and a Dual Phase Extraction system. HAZCO has been providing this full time operations service at this site for the past 3 years.

